

Copy 145

2 Pages

NPIC/R-251/64

April 1964

PHOTOGRAPHIC INTERPRETATION REPORT

ICBM COMPLEX, GLADKAYA, USSR, LAUNCH AREA B



CIA




DIA



NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER

Declass Review by NGA/DOD



TOP SECRET

NPIC/R-251/64

**ICBM COMPLEX, GLADKAYA, USSR,
LAUNCH AREA B**

25X1D

25X1
25X1D
This report, based on [] photog-
raphy through []
revises and updates NPIC/R-223/64, dated
April 1964. 1/

Launch Area B (56-24N 92-27E) consists
of a completed Type IID launch site and a site
support facility (Figure 1). It is located 20.4
nm northeast of the complex support facility
in a wooded area.

25X1D
25X1D
25X1D
This launch site was first identified in []
[] as a Type IIC launch site.
Its negation date could not be determined.
[] earth scarring
appeared at the launch site which was not
evident in []

25X1D
By [] it was
determined that the earth scarring was for the
canted and center buildings of a Type IID launch
site configuration. A detailed analysis revealed
that the Type IIC launch site had been abandoned
and the Type IID launch site had been superim-
posed over the original launch site.

25X1D
In [] the Type
IID launch site had progressed to a late stage
of construction and was considered complete

[] Orientation
of the pads is on an azimuth of 5 degrees, plus
or minus 5 degrees. One missile-ready building
is present and is 600 feet behind the right pad.
It is earth-banked and canted outward about
10 degrees. The 4 canted buildings and at
least 3 of the 4 center buildings are earth
mounded. An image visible on each pad is
probably the erector/shelter. Two other build-
ings are discernible within the launch site.
Security fencing is not apparent.

25X9
[]
Three buildings are along the north side
of the access road.

The site support facility is 0.7 nm west of
the launch site. It consists of an administra-
tion and housing section and a housing section.
The administration and housing section contains
48 buildings, 29 of which are barracks-type
buildings. The housing section contains 7 build-
ings, including 2 barracks-type buildings.

A power trace extends to the site support
facility from the southwest.

REFERENCES

25X1D
MAPS OR CHARTS

SAC. US Air Target Chart, Series 200, Sheet 0159, 22-HL, 2d ed, Nov 61, scale 1:200,000 (SECRET)

ACIC. ONC E-7, 1st ed, 15 Aug 61, scale 1:1,000,000 (CONFIDENTIAL)

DOCUMENT

1. NPIC. R-223/64, *ICBM Complex, Gladkaya, USSR*, Apr 64 (TOP SECRET [])

REQUIREMENT

GMAIC. UGMC 14-64

NPIC PROJECT

N-299/64

25X1

NPIC/R-251/64

25X1D




FIGURE 1. GLADKAYA LAUNCH AREA B.

NPIC H-9560 (4/64)

~~TOP SECRET~~
Approved For Release 2006/01/17 : CIA-RDP78B04560A002200010010-3

Approved For Release 2006/01/17 : CIA-RDP78B04560A002200010010-3
~~TOP SECRET~~